

SECTION 01015 — SCOPE OF WORK

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Work included in this package
- B. Drawing list

1.02 WORK INCLUDED IN THIS PACKAGE

- A. The work of this package shall include all labor, material, tools, equipment, shoring and temporary bracing, hoists, scaffolding and services needed to perform all the construction work, functional testing, and commissioning indicated on the drawings and/or described in the specifications, or that may be reasonably inferred as being necessary for the completion and serviceability for the intended use of all items of work, which includes but is not necessarily limited to the following:
 - A.1 Remove and dispose of all existing preformed metal siding (Honeycomb panel) and replace with new composite metal building panels (foam panels) around Building 663.
 - A.2 Remove and dispose of all existing louvers, louver doors, and fascia at the main entrance, and replace with new. Louver doors shall include associated new hardware and lock sets similar to existing.
 - A.3 Remove and reinstall all electrical, plumbing, mechanical items, and signs associated with the building envelope that will interfere with the replacement work such as exterior light fixtures, electrical outlets, and hose bibbs.
 - A.4 Repaint all surfaces not replaced in accordance with these specifications, such as stucco soffits, exit doors, door transoms, door frames, aluminum soffit panels, and like items.
 - A.5 Existing storefront glass and frames shall remain.
 - A.6 Siding for Building 664 is not included in this scope of work.
- B. Joint Occupancy: The Contractor is advised that the Government will require continuing joint occupancy of the facility and close coordination of work with other Contractors for facility construction. Such coordination will be facilitated by the Contracting Officer's Representative (COR), who will make decisions whenever conflicts arise.

1.03 DRAWING LIST

- A. The following drawings are incorporated as part of this work (reference attachment 1):

PLA2005-0663-001DA	T-1	Title, Site Plan Vicinity Map & Index of Drawings
PLA2005-0663-002DA	A-1	Existing Floor Plan
PLA2005-0663-003DA	A-2	Elevations
PLA2005-0663-004D	A-3	Window Details

- B. The following drawings are included as reference (reference attachment 1):

PLA94-663-002D	A-1	Medical Vestibule
PLZ86-663-004JB	A-4	Ground Floor Plan
PLZ86-663-006JA	A-6	Roof Plan and Details
PLZ86-663-007J	A-7	Exterior Elevations
PLZ86-663-008JA	A-8	Building Sections, Wall Sections & Details
PLZ86-663-009J	A-9	Wall Panel Details, Window Schedule, Louver Schedule & Details
PLZ86-663-010JB	A-10	Spaceframe and Storefront Plans, Elevation, Sections & Details
PLZ86-663-011JB	A-11	Spaceframe & Storefront Plans, Section & Details
PLZ86-663-012JA	A-12	Door Schedule, Details
PLZ86-663-014J	A-14	Reflected Ceiling Plan

PART 2 PRODUCTS

Not used

PART 3 EXECUTION

Not used

END OF SECTION